



AHM CAST MARBLE PRODUCTS MUST BE STORED INSIDE IN THEIR ORIGINAL PACKED CRATES UNTIL INSTALLATION TO BE DONE. ALL CAST MARBLE PRODUCTS TO BE INSTALLED WITHIN 45 DAYS AFTER THE MATERIAL ARRIVES ON SITE.

MATERIAL STORAGE ON SITE:

AHM's Cast marble products come in packed wooden crates. The wooden crates are designed to safely transport the material to the desired location / facility, but are not designed to store for an extended time. If the material is stored beyond the given time frame it can cause the material to warp or bow, due to which the installation cannot be done appropriately and can further lead to breakage (particularly of the Panels). Once the crates are unloaded from the Container, they should be stored indoors under maintained temperature. If the material is going to be installed after a certain period of time then it needs to be stored on a flat surface and to be covered with heavy industrial waterproof tarp. AHM is not responsible for the replacement of material that has been stained, dis-coloured, or damaged if stored unprotected. Special care should be taken if the storage facility is below 50 degree F, as the panels are more receptive to breakage while handling in cold temperatures.

NOTE:

- A container facility on site for storing Shower surrounds & Shower Pans for properties who do not have enough storage area

- Avoid direct sunlight on Shower panels, Shower Pans & Accessories.

MATERIAL HANDLING ON SITE:

The forklift will play a pivotal role in transferring the crates to a specifically designated area, facilitating the stacking process. Care should be taken not to exceed a stack of 4 crates atop one another. Going beyond this limit could result in excessive weight, jeopardizing the integrity of the crates and consequently the panels housed within. Furthermore, it is advised to refrain from attempting to unload more than a single crate simultaneously, ensuring a controlled and safe handling procedure.

To handle the material packed in wooden crates a qualified forklift operator and forklift with a minimum lift capacity of 5000 lbs and forks at least 72" in length is required as the crate size for the panels are long. Also a Pallet jack with a minimum load capacity of 4000 Lbs & 48" Long is required to move the crates and wooden pallets for materials delivered in 20 Ft and 40 Ft Containers.

NOTE:

- To have a Forklift on site at the time of unloading the crates from the container. Min capacity: 5000Lbs with 72" Forks.